

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25008-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 19-16S-11W  
1030 feet from N Section Line, 850 feet from W Section Line  
Lease Name: HOFFMAN Well #: 1  
County: BARTON Total Vertical Depth: 3410 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 4514 COLE AVE., STE 740, LB 30  
DALLAS, TX 75205

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| SURF   | 8.625 | 380        |             |         |

\$ 110.83

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/25/2007 12:00 AM  
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.  
Proposal Rcvd. from: DARRELL KRIER Company: SOUTHWIND DRILLING, INC. Phone: (620) 564-3800

Proposed Plugging Method: Ordered 155 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS Witness Type: NONE  
Date/Time Plugging Completed: 01/25/2007 5:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

1st. Plug at 3344' w/25 sxs.  
2nd. Plug at 740' w/25 sxs.  
3rd. Plug at 430' w/80 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.

INVOICED  
DATE 2-1-07  
INV. NO. 2007061294

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

*Marvin Mills*

(TECHNICIAN)

RECEIVED  
Form CP-2/3

JAN 31 2007

KCC WICHITA

JAN 26 2007

*PKS*