

15-059-19982-0020

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER ~~15-059-90512~~

SESWSW Sec/Twp/Rge 3-16S-21E

167 feet from south section line

4097 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: ~~STATE OF KANSAS~~ KCC

Name & FEE FUND

Address

AB oil well Gas Well SWD Well/ Input Well E 7526 D & A

Other well as hereinafter indicated:

Plugging Contractor: K-W OIL WELL SERVICES, INC. Lic. # 3097

Address: 19450 FORD ROAD CHANUTE, KS. 66720

Company to plug at: Hour: Day: 2 Month: AUGUST 2006

Plugging proposal received from: SAM KEPLEY

Company Name: KW OIL WELL SERVICES, INC. Phone: 620-496-7173

Were: PLUG WELL WITH PORTLAND CEMENT, TD TO SURFACE.

Plugging Proposal Received by: FRANK GUILFOYLE

Plugging attended by Agent: All Part X None

Operations Completed: Hour: Day: 3 Month: AUGUST 2006

Actual Plugging Report: LOCATE AND DIG UP WELL. CUT OFF 3 FT BELOW GROUND. SET

12" SURFACE TO TOP OF GROUND. WASH 1" DOWN 20 FT. HIT SOMETHING AND COULDN'T GET

DEEPER. START DRILLING. DRILL ROCK AND SOME SOFT CEMENT. DRILL AND WASH TO 400 FT.

PULL OUT, MOVE DRILL RIG, PULLING UNIT RAN 400 FT OF 1" BACK. PUMP PORTLAND CEMENT

FROM THERE TO SURFACE. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 163 SACKS OF

CEMENT. WELL PLUGGED.

Remarks: CONTROL # 20060051-012 GPS# 23 CONTRACT # 09379

(If additional description is necessary, use BACK of this form.)

I DID/PART observe this plugging.

Signed:

FRANK GUILFOYLE

TECHNICIAN

RECEIVED
SEP 20 2006
KCC WICHITA

KCC