

8-18

102
R

4-041436

15-147-00609-00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: ~~15-147-97,569~~
NE SE SE
~~SW NW NW~~ /4 SEC. 32, 05 S, 20 W
4290 990 feet from S section line
4950 330 feet from E section line
KCC 02-05-07 AB

Operator license# 5447 Lease Ray A well # 7

Operator: OXY USA, Inc. County Phillips

Address: 110 S. Main Well total depth 3573 feet
#800 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 198 feet
w/250 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 18 Month: August Year: 92

Plugging proposal received from: Jim Newell

Company: OXY USA, Inc. Phone: 913-434-7681

Were: 5 1/2" casing set @ 3566' w/150 sx. cement. Perf. @ 1667'.
Dakota @ 801'. Ordered 350 sxs. 60/40 pozmix - 10% gel. with 1/4#
F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 2:15P.M., Day: 18, Month: August, Year: 92

Actual plugging report: R.I.H. with perf. to perf. @ 1667' and 1050'
with 4 S.P.F. R.I.H. with tubing to 3490'. Staged cement to surface.
P.O.O.H. with tubing and pumped a total of 300 sxs. 60/40 pozmix -
10% gel. with 1/4# flocele plus 300# hulls. Max. 650# P.S.I.
S.I. 450# P.S.I. Hooked-up to 8 5/8" S.P. and pumped in 50 sxs.
60/40 pozmix - 10% gel. with 1/4# F.C. in cement. Max. 350# P.S.I.
S.I. 150# P.S.I.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did X / did not observe the plugging.

Dennis L. Hamel (agent)

INVOICED
DATE 1-11-93
INV. NO. 37177
8-18-92

JAN 22 1993

RECEIVED
STATE CORPORATION COMMISSION
1-6-93
6 1993
CONSERVATION DIVISION
Form CP-2/3