

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Merit Energy Company

Address: 13727 Noel Road, Ste. 500, Dallas, TX 75240

Phone: (972) 628-1659 Operator License #: 32446

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)
by: Doug Louis (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 095-20616 -00-00

Lease Name: West Spivey Unit (T Jaden G-2) PPT

Well Number: 1

Spot Location (QQQQ): Se - SW
110 710 Feet from North / South Section Line
4300 1980 Feet from East / West Section Line

Sec. 13 Twp. 30 S. R. 8 East West

County: Kingman

Date Well Completed: _____

Plugging Commenced: 01/04/07

Plugging Completed: 01/05/07

KCC
PPT
2/26/07
per
Eli Sa
beth

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	250	
				5 1/2"	4315	3430

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded off bottom, loaded hole with water, dug cellar, unpacked casing head, set floor, checked holed, sand at 4210', bailed 5 sx cement, pulled slips, cut casing head off 4' below ground, had 31" stretch, ripped casing at 3430', came free, pulled up to 1250', pumped 35 sx cement at 1250', pulled to 700', pumped 35 sacks, pulled to 300', circulated with 140 sx to surface, pulled casing out, topped off with 10 sx

Name of Plugging Contractor: Quality Well Services License #: 31925

Address: 401 W. Main St., Lyons, KS 67554

Name of Party Responsible for Plugging Fees: Merit Energy Company

State of Texas County, Dallas, ss.

Elizabeth Lyon (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____
(Address) 13727 Noel Road, Ste. 500, Dallas, TX 75240



SUBSCRIBED and SWORN TO before me this 26 day of January, 20 07

My Commission Expires: 11/24/09

RECEIVED

JAN 29 2007

KCC WICHITA