

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form GP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: _____ (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Tarkio Sand Depth to Top: 2431 Bottom: 2520 T.D. _____
Toronto, LKC Depth to Top: 3008 Bottom: 3281 T.D. _____
Arbuckle Depth to Top: 3323 Bottom: 3325 T.D. _____

API Number: 15 - 167-20710-00 - 00

Lease Name: Eichman A

Well Number: #22

Spot Location (QQQQ): NE - SE - SE -
990' Feet from North / South Section Line

330' Feet from East / West Section Line

Sec. 12 Twp. 15 S. R. 14 East West

County: Russell

Date Well Completed: 1/75

Plugging Commenced: 1/11/07

Plugging Completed: 1/11/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	361	8 5/8	361	0
	Production	Surface	3323	5 1/2	3323	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RU Quality Oilwell Cementing. Pumped 600# hulls & 235 sx 60/40 Poz w/10% gel @ 1550'. TOH w/50 jts 2 3/8" tbg. Hooked up to 8 5/8" surface. Pressured to 500 psi and held. Swedged into 5 1/2" csg. Pumped 25 sx 60/40 Poz w/10% gel. Pressured to 700 psi. SI csg. Plug job witnessed and approved by Case Morris w/KCC, Hays.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606


Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Susan Sears, Operations Engineer (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Susan W. Sears

(Address) 250 N. Water, Suite 300; Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 25th day of January, 20 07

Susan Brady My Commission Expires: 11-4-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
JAN 29 2007
KCC WICHITA