

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: AMERICAN WARRIOR, INC.
Address: P.O. Box 399 Garden City, KS 67846
Phone: (620) 275-9231 Operator License #: 4058
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 1/7/07 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
None Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 065-23,264-00-00
Lease Name: FAULKNER
Well Number: 1-27
Spot Location (QQQQ): Ne - SW - SE - SW
340 Feet from North / South Section Line
1790 Feet from East / West Section Line
Sec. 27 Twp. 10 S. R. 22W East West
County: Graham
Date Well Completed: 1/8/07
Plugging Commenced: 4:15PM 1/8/07
Plugging Completed: 7:45PM 1/8/07

KCC
PPT
2-6-07
per
CP213

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surface	211	8 5/8	211.63	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @ 3925'W/25sks 5th Plug @ 40'W/10sks Circulated 1st Plug 15 Minutes W/56Vis MUD
2nd Plug @ 1825'W/25sks 15sks In Rat hole Plugs Displaced with Mud
3rd Plug @ 1025'W/100sks 10sks In Mouse Hole Total 215sks 60/40Poz 6%Gel W/1/4#CF/sk
4th Plug @ 275'W/40sks By Allied Cementing Completed @ 7:45PM 1/8/07

Name of Plugging Contractor: Discovery Drilling Co., Inc. License #: 4058 31548
Address: P.O. Box 763 Hays, KS 67601
Name of Party Responsible for Plugging Fees: AMERICAN WARRIOR, INC.

PPT
2/6/07

State of Kansas County, Finney, ss.
Nancy E Davis, Compliance Coordinator (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
(Address) 40 AWZ, P.O. Box 399, Garden City, KS 67846

SUBSCRIBED and SWORN TO before me this 27th day of January, 2007
Erica Kuhlmeier My Commission Expires: 09-12-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
JAN 30 2007
KCC WICHITA
PPT