

15-163-00278-00-00

WELL PLUGGING RECORD

NORTH

Name of Conservation Agent who supervised plugging of this well..... C. D. Stough.....

Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... 3665..... Feet

Show depth and thickness of all water, oil and gas formations.

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Bottom plug set at 160' with 15 sacks cement.
Top plug set at 35' with 10 sacks cement.

Received

8/24/50
AUG 24 1950

ST. 12-1-1000

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anschutz Drilling Company, Inc.
Address 709 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
M. W. Smith (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. [illegible]
709 Union Nat'l Bank, Wichita, Kansas

SUBSCRIBED AND SWORN to before me this 23rd day of August 1950

My commission expires Jan. 21, 1954 Patricia Meeker Notary Public.

28-32

PLUGGING

FILE SEC 27 T 9 R 186

BOOK PAGE 28 LINE 13

23-3273-s 4-50-10M

DRILLERS' LOG

Fred B. Anschutz - #1 McConchie
NE NE NW - Section 27-9S-18W
Rooks County, Kansas

0	170	Shale
170	760	Shale & shells
760	875	Sand
875	1000	Shale & shells
1000	1020	Shale & shells
1020	1160	Sand
1160	1480	Shale & Redbed
1480	1490	Redbed
1490	1530	Anhydrite
1530	2285	Shale & shells
2285	2400	Lime & shale
2400	2750	Lime & shale
2750	2875	Shale & shells
2875	3110	Shale & shells
3110	3333	Lime & shale
3333	3360	Lime
3360	3410	Lime
3410	3590	Lime
3590	3640	Conglomerate
3640	3665	Conglomerate
3665		ROTARY TOTAL DEPTH

COMMENCED: 8/5/50
COMPLETED: 8/15/50

TOPS:

Top.	3110
Heeb.	3326
Tor.	3348
Lans.	3366 (-1202)
Cong.	3593 (-1484)
RTD	3665 In Conglomerate

CASING RECORD

Set 8-5/8" surface casing
at 163' w/100 sacks & 1 CC.

D & A

STATE OF KANSAS)
COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 McConchie located in the NE NE NW of Section 27-9S-18W, Rooks County, Kansas.

ANSCHUTZ DRILLING CO., INC.

By:

M. W. Smith

8/24/50
950

Subscribed and sworn to before me this 23rd day of August, 1950.

Laurina Reeker
Notary Public

My commission expires January 21, 1954.

