


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks County, Sec. 18 Twp. 9S Rge. 18W (E) (W)
Location as "NE/CNWKSWK" or footage from lines SE NW NW
Lease Owner: Murfin Drilling Co.
Lease Name: Bedard #1 Well No. _____
Office Address: Russell, Kansas 67665
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 8/8/73 _____ 19____
Plugging completed 8/11/73 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3523 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3519	2488

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, pushed plug to 3000', ran 10' sand and dumped 5 sacks cement. Shot pipe at 2590', 2495', pulled 34 joints black pipe and 42 joints plastic pipe. Squeezed well with 5 sacks hulls, 35 sacks gel and 120 sacks pos with 6% gel.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
AUG 21 1973
8-21-73
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of August, 19 73

My commission expires _____

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

ROTARY DRILLING LOG

Operator: D & D Drilling Company, Inc., & Lee Phillips Oil Company
Contractor: D & D Drilling Company, Inc.
Comm: 10-21-63
Comp: 10-30-63

Well: Bedard No. 1
Location: SE NW NW Sec. 18-9S-18W
County: Rooks County, Kansas
Elevation: 2096 K.F.

Formations	Depth	Remarks
Shale	216'	Ran 6 joints of 8 5/8" casing set at 216' with 17" sx.
Shale & Sand	965'	
Sand	1175'	
Shale	1460'	
Anhy.	1510'	
Shale	1570'	
Shale & Shells	1810'	
Shale	2110'	
Shale & Lime	2280'	
Lime & Shale	3290'	
Lime	3523'	
Rotary Total Depth	3523'	Set 5 1/2" casing at 3519' cemented with 150 sx salt cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1973
8-10-73
CONSERVATION DIVISION
Wichita, Kansas

A F F I D A V I T

State of Kansas)
) SS
County of Sedgwick)

James R. Daniels, of lawful age, being duly and solemnly sworn on oath says: I am a resident of Wichita, Sedgwick County, Kansas, and I hereby know and on oath state, the above drilling log covering the Bedard No. 1 located in the SE NW NW of Section 18-9S-18W, Rooks County, Kansas is true and correct to the best of my knowledge and belief. Further affiant saith not.

D & D Drilling Company, Inc.

By: James R. Daniels
James R. Daniels

Subscribed and sworn to before me this 1st day of November, 1963.

My commission expires 11-18-66

Constance J. Apple
Constance J. Apple - Notary Public