


All Information Completely
Required Affidavit
For Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Rooks County, Sec. 18 Twp. 9S Rge. 18W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NE NW

Lease Owner D & D Drilling Company, Inc.

Lease Name Bedard Well No. 3

Office Address 307 Schweiter Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-2-64 19

Application for plugging filed 6-8-64 19

Application for plugging approved 6-2-64 19

Plugging commenced 6-2-64 19

Plugging completed 6-2-64 19

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3567 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing		0	226'	8 5/8"	5-27-64	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy drilling mud. Set Plug #1 at 550' with 20 sacks cement. Set Plug #2 at 210' with 20 sacks cement. Set Plug #3 at 35' with 10 sacks of cement and 1/2 sack hulls.

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1964
6-10-64

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D & D Drilling Company, Inc.

Address 307 Schweiter Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

James R. Daniels (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James R. Daniels (Address)

SUBSCRIBED AND SWORN to before me this 8th day of June, 19 64

My commission expires 11-18-66

Colleen Chapple
Colleen Chapple Notary Public.



ROTARY DRILLING LOG

OPERATOR: D & D Drilling Co., Inc. COMM: 5-25-64
 CONTRACTOR: D & D Drilling Co., Inc. COMP: 6-2-64
 WELL: Bedard No. 3 ELEV: 2108 K.B.
 LOCATION: SW NE NW Sec. 18-9S-18W
 COUNTY: Rooks County, Kansas

FORMATION	DEPTH	REMARKS
Shale & Sand	1200'	Set 9 joints of 8 5/8" at 226' cemented with 200 sacks Sunset.
Shale & Shell	1490'	
Anhy.	1530'	
Shale	1880'	
Shale & Lime	2480'	
Lime & Shale	2754'	
Lime	2840'	
Lime & Shale	3315'	
Lime	3567'	
Rotary Total Depth	3567'	D & A

RECEIVED
 STATE CORPORATION COMMISSION

JUN 10 1964
 6-10-64
 CONSERVATION DIVISION
 Wichita, Kansas

A F F I D A V I T

State of Kansas)
) SS
 County of Sedgwick)

I, James R. Daniels of lawful age, being duly and solemnly sworn on oath says: I am a resident of Wichita, Sedgwick County, Kansas, and I hereby know and on oath state, the above drilling log covering the Bedard No. 3 located in the SW NE NW of Section 18-9S-18W, Rooks County, Kansas is true and correct to the best of my knowledge and belief. Further affiant saith not.

D & D DRILLING COMPANY, INC.

By: James R. Daniels
 James R. Daniels

Subscribed and sworn to before me this 8th day of June, 1964.

My Commission Expires
11-19-66

Colleen Chapple
 Colleen Chapple - Notary Public

