

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-01539-00-00

API NUMBER NA

LEASE NAME Hilgers B

WELL NUMBER 2

SPOT LOCATION SW/4 SW/4 NE/4

SEC. 18 TWP. 9 RGE. 18 (X) or (W) SW/4

COUNTY Rooks

Date Well Completed 11-11-56

Plugging Commenced 10-29-85

Plugging Completed 11-5-85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS 801 Union Center Wichita, KS 67202

PHONE # (316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing formation Arbuckle - LKC Depth to top 3064' bottom 3532' T.D. 3532'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Oil/ Content	From	To	Size	Put in	Pulled out
Lansing KC	water 3064-66	3296	98	8 5/8	141'	None
	3195-99	3319	22	4 1/2"	3527'	None
	3215-18	3342	44			
	3286-88	3369	73			
Arbuckle	Oil water	3529	32			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 10-29-85 Plug well with 50 sxs 60/40 poz 6% gel; 10 sxs gel with 3 sxs hulls; cap with 150 sxs 60/40 poz 6% gel 1 sx hulls with 300# standing. Annulus - 120 sxs 60/40 poz 6% gel 200# pressure.

11-5-85 Cement top 100' KB - plug back to surface - 1 yard ready mix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor A. L. Abercrombie, Inc. License No. 5393

Address 801 Union Center Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton, Vice President (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 21 day of November 1985

Sherrie L. Brooks Notary Public
STATE CORPORATION COMMISSION

My Commission expires: 08-21-86

Sherrie L. Brooks

NOV 22 1985
11-22-85
CONSERVATION DIVISION

DRILLERS' LOG

NAME: HILGERS "B" #2 DATE SPUDDED: 11-11-56
LOCATION: SW/4 SW/4 NE/4 SW/4 Sec.18-9S-18W ROTARY COMPLETED: 11-19-56
Rooks County, Kansas ELEVATION: 2110 RB
OPERATOR: Osage Oil & Gas Co. 2108 DF
CONTRACTOR: Heathman-Seeligson Drilling Co. ROTARY TOTAL DEPTH: 3532'
SURFACE CASING: Ran 7 jts. 8-5/8 used csg. cemented
at 140.51' w/145 sacks of sack
cement and 2 Calcium Chloride.
OIL STRING: Ran 111 jts. 5-1/2 casing cemented
at 3532' w/175 sacks of bulk cement.

DRILL STEM TESTS

#1 3527-32 open 1 1/2 hrs., closed in
20 min., rec. 200' oil and
8' oily mud. BHP-1005#, IFP-0#,
FFP-0#.

GEOLOGICAL TOPS (RB)

Anhydrite	1480 (/630)
Topeka	3037 (-927)
Heebner	3245 (-1135)
Toronto	3266 (-1156)
Lansing	3284 (-1174)
Arbuckle	3525 (-1415)
R.T.D.	3532

L O G

(Figures indicate bottom of formation)


Clay, Sand & Rock	0 - 40
Shale & Shells	700
Shale & Sand	980
Sand	1180
Shale & Red Bed	1330
Sand & Red Bed	1470
Anhydrite	1515
Shale & Shells	2100
Shale & Lime	3283
Line	3532

The undersigned, H. D. Shreve, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Report.

HEATHMAN-SEELIGSON DRILLING CO.

By: 

Subscribed and sworn to before
me the 29th day of November, 1956.


Patricia W. Lamkin, Notary Public

My commission expires: April 3, 1960

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1985

CONSERVATION DIVISION
Wichita, Kansas