

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

18W

Rooks County. Sec. 18 Twp. 9S Rge. 18 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C. NW $\frac{1}{4}$ NW $\frac{1}{4}$ NE $\frac{1}{4}$
Lease Owner. Harry Gore
Lease Name. Peck Well No. 1
Office Address. 400 Brown Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed. Feb. 2, 1947
Application for plugging filed. 19
Application for plugging approved. 19
Plugging commenced. Feb. 3, 1947
Plugging completed. Feb. 3, 1947
Reason for abandonment of well or producing formation.
If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well.
Producing formation. none Depth to top. -- Bottom. -- Total Depth of Well. 3630 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	Surface 8 jts. @ 257'	none
						No oil string of casing run.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to bottom of surface pipe with heavy mud; set bottom plug @ 255' put 15 sacks of cement on bottom plug. Filled with heavy mud to 30' of top of hole; set top plug @ 30' filled with cement to bottom of cellar or 10 sacks of cement used.

18 9 18W
96 43



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Harry Gore
Address. 400 Brown Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
H H & B Drilling Co., Inc. (employee of owner)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

H H & B DRILLING CO., INC.
BY: R. W. Bailey, Asst. Sec.
705 Petroleum Bldg., Wichita, Kansas

SUBSCRIBED AND SWORN to before me this 5th day of February, 1947

My commission expires July 2, 1949

Richard Hindery
Notary Public.

PROG WELL NO. 1

Location: Approx. Center NW $\frac{1}{4}$ NW $\frac{1}{4}$ NE $\frac{1}{4}$ Sec. 18-9S-18W
Rooks County, Kansas
Commenced: 1-19-47

Owner: Harry Gore Oil String Cemented: none

Contractor: H H & B Drilling Co., Inc.

Casing Records: Surface Casing - 8 Jts. 10-3/4" 8 Rd. Thd. 32# @ 257'
Cemented with 135 sacks Lone Star Cement
Oil String - none run Total Depth: 3630'
Abandoned: 2-3-47

LOG

(Figures indicate bottom of formation)

Clay Shale and shells	0 to 45	Lime	2710
Sand, shale and shells	200	Shale and lime	2760
Shale and shells	255	Lime and shale	2855
Shale	480	Lime and shale	2900
Shale	565	Shale	3010
Sand	610	Shale	3025
Shale, sand and shells	930	Lime	3070
Sand and shells	1180	Lime	3125
Red bed, shale and shells	1290	Lime	3158
Red bed	1460	Lime and shale	3195
Anhydrite	1495	Lime	3235
Shale	1540	Lime	3270
Shale and shells	1690	Lime	3300
Shale and shells	1800	Lime	3325
Shale and shells	1910	Lime	3385
Lime	1955	Lime and shale	3420
Lime and shale	2030	Lime	3437
Shale and lime shells	2100	Lime	3470
Lime and shale	2170	Lime and shale	3503
Lime and shale	2215	Lime	3520
Lime and shale	2305	Lime and chert	3550
Lime and shale	2380	Chert	3581
Lime and shale	2455	Chert	3590
Shale and lime shells	2515	Conglomerate	3602
Shale and shells	2595	Arbuckle	3615
Shale and lime	2655	Arbuckle	3630
Lime and shale	2695	Total Depth	3630'

18 9 18W
96 43

The undersigned, H H & B Drilling Co., Inc., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

H H & B DRILLING CO., INC.

BY: Richard W. Bailey
Asst. Secretary

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

Be it remembered that on this 5th day of February, 1947, before me the undersigned, a Notary Public, duly commissioned, in and for the County and State aforesaid, came R. W. Bailey, Asst. Secretary of H H & B Drilling Co., Inc., a corporation of the State of Kansas, personally known to me to be such officer, and to be the same person who executed as such officer the foregoing instrument of writing in behalf of said corporation, and he duly acknowledged the execution of the same for himself and for said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

Richard W. Bailey
Notary Public

My commission expires: July 2, 1949