

11-21-85  
NOV 21 1985  
15-163-19285-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA  
LEASE NAME Hilgers B

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1  
SPOT LOCATION SW NW SE SW

LEASE OPERATOR A. L. Abercrombie, Inc.  
ADDRESS 801 Union Center, Wichita, KS 67202

SEC. 18 TWP. 9 RGE. 18 (X) or (W)  
COUNTY Rooks

PHONE # (316) 262-1841 OPERATORS LICENSE NO. 5393

Date Well Completed 8-16-56

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Commenced 10-29-85

Plugging Completed 11-5-85  
KCC  
AB

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? Yes

Producing formation Arbuckle LKC Depth to top 3284 bottom 3535 T.D. 3535

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing KC	Oil and water	3284	88	8 5/8	196'	None
	Oil and water	3326	24	5 1/2"	3532	None
	Oil and water	3343	47			
	Oil and water	3369	73			
Arbuckle	Oil and water	3532	35			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 10-29-85 Plug well from 2480' to surface with 50 sxs 60/40 poz with 6% gel; 20 sxs gel; 2 sxs hulls; cap with 150 sxs 60/40 poz 6% gel; 1 sx hull with 200# standing. Plug annulus with 30 sxs 60/40 poz 6% gel 800\$ pressure.

11-5-85 Top cement 300' KB. Cap to surface with 2 1/2 yds ready mix.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor A. L. Abercrombie, Inc. License No. 5393  
Address 801 Union Center Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton, Vice President (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton  
(Address) 801 Union Center, Wichita, Ks 67202

SUBSCRIBED AND SWORN TO before me this 21 day of November, 19 85

My Commission expires: 08-21-86

Sherrie L. Brooks RECEIVED  
Notary Public  
Sherrie L. Brooks  
11-22-85  
NOV 22 1985  
STATE CORPORATION COMMISSION

# WELL LOG

15-163-19285-00-00

COMPANY OSAGE OIL & GAS COMPANY

SEC. 18 T. 9S R. 18W

FARM Hilgers

NO. P # 1


LOC. SW, NW, SE, SW

TOTAL DEPTH 3535'

COUNTY Rooks Co., Kansas

COMM. August 9, 1956 COMP. August 16, 1956

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 196' W/125 sax.  
5 1/2" @ 3532' W/175 sax.  
Stage collar @ 1515' W/250 sax.

ELEVATION 2121' RB.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

100	Postrock & clay	Anhydrite	1488
196	Shale	Hebn.	3246
1488	Shale & sand	Toronto	3265
1530	Anhydrite	Lansing	3284
2200	Shale & shells	Arbuckle	3529
3270	Shale & lime		
3535	Lime		
3535	T. D.		

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 19 1985  
CONSERVATION DIVISION  
Wichita, Kansas

State of KANSAS }  
County of BARTON } ss:

I, Verne A. Morris of Garvey Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Hilgers well

Verne A. Morris

Subscribed and sworn to before me this 23rd day of August 19 56

My Commission Expires: July 11, 1960

Zed J. Brawn  
NOTARY PUBLIC