

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

RECEIVED

Form CP-1
September 2003

WELL PLUGGING APPLICATION

KANSAS CORPORATION COMMISSION

This Form must be Typed
Form must be Signed
All blanks must be Filled

Please TYPE Form and File ONE Copy

MAR 23 2004

API # 15-015-22501-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 2-27-84

Well Operator: WHITE PINE PETROLEUM CORPORATION KCC License #: 5044
(Owner / Company Name) (Operator's)

Address: 110 S. MAIN, SUITE 500 City: WICHITA

State: KANSAS Zip Code: 67202 Contact Phone: (316) 262-5429

Lease: MURRAY Well #: 6 Sec. 30 Twp. 25 S. R. 5 East West

NW SE SW Spot Location / QQQQ County: BUTLER

990 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1650.9630 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # D-23126 ENHR Docket # _____ Other: _____

Conductor Casing Size: none Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 264 Cemented with: 100 Sacks

Production Casing Size: 5 1/2" Set at: 2695 Cemented with: 175 Sacks

List (ALL) Perforations and Bridgeplug Sets: OPEN HOLE COMPLETION

Elevation: 1401 (G.L. / K.B.) T.D.: 3217 P.B.T.D.: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): sand back to 2645, dump 6 sx cement on top of sand, work pipe to recover approximately 1200', run in to 315 set top plug. Run tubing in to top of plug and pump cement to surface. pull tubing, fill cellar

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: WILBUR C. BRADLEY

Phone: (316) 262-5429

Address: 110 S. MAIN, SUITE 500 City / State: WICHITA, KS 67202

Plugging Contractor: GLACIER WELL SERVICE KCC License #: 5721

Address: P O BOX 577, EMPORIA, KS 66801 Phone: (620) 342-1148
(Company Name) (Contractor's)

Proposed Date and Hour of Plugging (if known?): as soon as the rig is available

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/23/04 Authorized Operator / Agent: Wilbur C Bradley
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

White Pine Petroleum Corporation
110 S. Main St., Suite 500
Wichita, KS 67202-3745

April 14, 2004

Re: MURRAY #6
API 15-015-22501-00-00
NWSESW 30-25S-5E, 990 FSL 3630 FEL
BUTLER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
130 S. Market, Room 2125
Wichita, KS 67202-3208
(316) 337-6231

Sincerely



David P. Williams
Production Supervisor