

RECEIVED

JUN 21 2004

KCC WICHITA

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

15-115-20190-00-001

API # 4/20/1974 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Hillenburg Oil Company KCC LICENSE # 5375 *6/05*
(owner/company name) (operator's)

ADDRESS 11600 S. Lynn Lane Road CITY Broken Arrow

STATE Oklahoma ZIP CODE 74011 CONTACT PHONE # (918) 455-4444

LEASE Reamey WELL# 34 SEC. 20 T. 21 R. 4 (East/West)

NW - NE - NE - SPOT LOCATION/QQQQ COUNTY Marion

4950 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A (SWD) ENHR WELL DOCKET# D-25001
9/24/86 1" Ran to 250' cemented to surface

CONDUCTOR CASING SIZE SET AT CEMENTED WITH 91 SACKS

SURFACE CASING SIZE 10 3/4 SET AT 103 CEMENTED WITH 125 SACKS

PRODUCTION CASING SIZE 7 SET AT 2584 CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perf (2376-2886) (2412-2417)B.P. at 2440

ELEVATION Approx. 1379 T.D. 3080 PSTD 2440 ANHYDRITE DEPTH -
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Per KCC rules and regulations

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? ?

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Richard Morris PHONE# (620) 628-4777

ADDRESS P.O. Box 337 603 S. Kansas City/State Canton, KS 67428-0337

PLUGGING CONTRACTOR Scott's Well Service, Inc. KCC LICENSE # 6819 *6/05*
(company name) (contractor's)


ADDRESS P.O. Box 136 Roxbury, KS 67476 PHONE # (785) 254-7828

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 6/10/04 1P.M. Plugged 6-10-04

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6-17-2004 AUTHORIZED OPERATOR/AGENT: Mark Hillenburg
(signature) *hm*

Dist 08



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

April 22, 1974

COMPANY: HILLENBURG OIL COMPANY
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: REAMEY #34
 LOCATION: NW NE NE, Sec. 20-21S-4E,
 Marion County, Kansas
 COMMENCED: April 13, 1974
 COMPLETED: April 20, 1974
 ELEVATION:

0	to	80	Lime
80	to	103	Blue Shale
103	to	675	Lime & Shale
675	to	1175	Shale
1175	to	1365	Shale & Lime
1365	to	1570	Lime & Shale
1570	to	1810	Shale
1810	to	2195	Lime
2195	to	2280	Lime Chert
2280	to	2408	Shale & Lime
2408	to	2508	Lime
2508	to	2566	Sand & Lime
2566	to	3080	Arbuckle
		3080	T. D.

Cut 15 1/4 inch hole to 103 ft. and run 103.75 ft. of 10 3/4 inch surface pipe, cemented with 125 sacks of cement at 103 ft., plug down at 7:00 p. m., April 13, 1974. Drilled 8 5/8 inch hole to 3080 ft. Run 2584 ft. of 7" o. d. casing, cemented with 150 sacks of cement at 2580 ft. Plug down at 1:30 P. M., April 20, 1974.

TOPS: ARBUCKLE - 2566'

Measurements taken from K. E.


CERTIFICATE

I, Charles D. Johnson, Secretary-Treasurer of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Reamey#34, located on the NW NE NE, Section 20-21S-4E, Marion County, Kansas as reflected by the files of Blackstone Drilling, Inc.

[Signature]
 Charles D. Johnson, Secretary-Treasurer

[Signature]
 Johnnie L. Schmidt - Notary Public

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 19th day of April, 1974.



RECEIVED
 JUN 21 2004
 KCC WICHITA