

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20461-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 36-15S-26W
2399 feet from S Section Line, 5026 feet from E Section Line
Lease Name: THORNBURG D Well #: 2
County: GOVE Total Vertical Depth: 4500 feet

Operator License No.: 7775
Op Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4500	0	w/unknown sxs cmt
SURF	8.625	325	0	w/200 sxs cmt

\$146.25

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/25/2007 8:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: WILSON JACKSON Company: WILTON PETROLEUM, INC. Phone: (620) 628-4466

Proposed Plugging Method: Ordered 225 sxs Swift Multi-Density Cement and 600# hulls.
Plug through casing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/25/2007 11:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 325' w/200 sxs cement.
4 1/2" production casing set at 4500' w/unknown sxs cement.
Perforated 4 1/2" casing at 975' and 2025'.
Connected to 4 1/2" production casing - pumped 175 sxs cement with 600# hulls.
Max. P.S.I. 500#. S.I.P. 0#.
Connected to 8 5/8" surface casing - pumped 20 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

INVOICED
DATE 2-6-07
INV. NO. 2007061310

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES CEMENT-TICKET #11696.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

JAN 26 2007

PKT