

O:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25605-00-00
Spot: SWNENWSE Sec/Twnshp/Rge: 10-14S-16W
2300 feet from S Section Line, 1900 feet from E Section Line
Lease Name: GLICK Well #: 1-10
County: ELLIS Total Vertical Depth: 3503 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	224		

\$ 113.85

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/19/2007 9:00 PM
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING
Proposal Rcvd. from: ELDO Company: ANDERSON, C. D. DBA ANDERSON Phone: (785) 421-2234

Proposed Plugging Method: Order 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 01/19/2007 11:30 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3450' w/25 sxs.
2nd. Plug at 1125' w/25 sxs.
3rd. Plug at 825' w/100 sxs.
4th. Plug at 275' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs:

INVOICED
DATE 2-7-07
INV. NO. 2007061317

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

FEB 06 2007

CONSERVATION DIVISION
WICHITA, KS

FEB 05 2007

RET