

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-22839-00-00
Spot: NW NENE Sec/Twnshp/Rge: 23-26S-9E
4799 feet from S Section Line, 810 feet from E Section Line
Lease Name: BURKETT Well #: 3
County: GREENWOOD Total Vertical Depth: 2208 feet

Operator License No.: 6980
Op Name: MCCLELLAND, LARRY DBA MCCLELL
Address: 729 PLOVER
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2186	0	
SURF	8.625	200	0	

\$ 71.76

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/18/2006 9:00 AM
Plug Co. License No.: 7719 Plug Co. Name: CHEEVER WELL SERVICE, INC.
Proposal Revd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' cement plug @ 2100' 50' cement plug @ 900' 200' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2006 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report: _____ Perfs: _____

ran tubing to 2045', pumped 20 sxs cement, pulled tubing to 900' shot casing , pumped 20 sxs cement, pulleed casing to 200' shot casing,pumped35 sxs cement to surface.pulled tubing out.

RECEIVED
KCC DISTRICT #3
JAN 29 2007 MH
CHANUTE, KS

INVOICED
DATE 2-6-07
INV. NO. 2007061305

Remarks:
Plugged through: TBG

District: 03 Signed Mike Heffern
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2007
CONSERVATION DIVISION
WICHITA, KS

PKF