

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-21798-00-00
Spot: SESENE Sec/Twnshp/Rge: 34-21S-38W
2200 feet from N Section Line, 625 feet from E Section Line
Lease Name: LOTTINVILLE FARMS Well #: 1-34
County: KEARNY Total Vertical Depth: 5400 feet

Operator License No.: 5249
Op Name: OSBORN HEIRS COMPANY, LTD
Address: PO BOX 17968
SAN ANTONIO, TX 78217

String Size Depth (ft) Pulled (ft) Comment
SURF 8.625 430

\$ 175.50

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/26/2007 6:00 AM
Plug Co. License No.: 33375 Plug Co. Name: CHEYENNE DRILLING, LP
Proposal Rcvd. from: DAVID Company: CROWN CONSULTING Phone: _____

Proposed Plugging Method: 1ST PLUG AT 2130' WITH 50 SX CMT. 2ND PLUG AT 1040' WITH 80 SX CMT. 3RD PLUG AT 480' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 01/26/2007 8:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 2130' WITH 50 SX CMT. 2ND PLUG AT 1040' WITH 80 SX CMT. 3RD PLUG AT 480' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:


INVOICED
DATE 2-6-07
INV. NO. 2007061307

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY HALLIBURTON.

Plugged through: DP

District: 01



Signed Eric MacLaren
(TECHNICIAN)

Form CP/E/S
[Handwritten signature]