

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21997-00-00
Spot: S2SWW Sec/Twnshp/Rge: 34-17S-30W
100 feet from S Section Line, 800 feet from W Section Line
Lease Name: GLENN SHARP Well #: 1
County: LANE Total Vertical Depth: 4585 feet

Operator License No.: 4767

Op Name: RITCHIE EXPLORATION, INC.

Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	236		

\$ 149.01

Well Type: DH

UIC Docket No:

Date/Time to Plug: 01/19/2007 8:00 AM

Plug Co. License No.: 5822

Plug Co. Name: VAL ENERGY, INC.

Proposal Rcvd. from: TIM

Company:

Phone:

Proposed Plugging Method: 1ST PLUG AT 2150' WITH 50 SX CMT. 2ND PLUG AT 1500' WITH 80 SX CMT. 3RD PLUG AT 840' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT

WitnessType: NONE

Date/Time Plugging Completed: 01/19/2007 5:00 PM

KCC Agent: STEVE DURRANT

Actual Plugging Report:

Perfs:


1ST PLUG AT 2150' WITH 50 SX CMT. 2ND PLUG AT 1500' WITH 80 SX CMT. 3RD PLUG AT 840' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

INVOICED
DATE 2-6-07
INV. NO. 2007061308

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Steve Durrant

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

FEB 02 2007

CONSERVATION DIVISION
WICHITA, KS

PKC