

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-22591-00-00  
Spot: W2NENENE Sec/Twnshp/Rge: 6-15S-13W  
4950 feet from S Section Line, 510 feet from E Section Line  
Lease Name: BERRICK COL Well #: 1  
County: RUSSELL Total Vertical Depth: 3150 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3149	0	85 SX
SURF	8.625	727	0	350 SX

\$ 102.38

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2006 10:00 AM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/22/2006 11:30 AM KCC Agent: CASE MORRIS

**Actual Plugging Report:**

Pressured backside to 500# P.S.I. Held.  
Tied onto casing - pumped 280 sxs 60/40 pozmix - 10% gel with 600# hulls.  
Max. P.S.I. 1200#. S.I.P. 600#.

**Perfs:**

Top	Bot	Thru	Comments
2923	3089		L-KC
2870	2875		DOUGLAS
2843	4247		TORONTO

**INVOICED**

DATE 2-12-07  
INV. NO. 2007061326

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

*M*

Signed \_\_\_\_\_

*Case Morris*

(TECHNICIAN)

RECEIVED

KANSAS CORPORATION COMMISSION

FEB 07 2007

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

JAN 26 2007

*PS*

TERRA RESOURCES, INC.  
P.O. BOX 839

#1 COL. BERRICK

6-15-13W

OKLAHOMA CITY, OK 73101

100'E


CONTR RED TIGER DRILLING

CTY RUSSELL

C N/2 NE NE

GEOL MIKE FLETCHER

FIELD HALL-GURNEY



ELV 1755 KB SPD 4/17/85 CARD ISSUED 6/27/85 IP P 16 BO & 100 BWPD  
1750 GL DRLG COMP 4/23/85 SHAW(TOR) 2843-2847  
API 15-167-22,591 DOUG 2870-2875  
LKC 2923-3089 OA

LOG	Top	Depth/Datum
GR HAV	.....	2254- 499
TARK	.....	2322- 567
SEV SH	.....	2577- 822
TOP	.....	2596- 841
HEEB	.....	2824-1069
TOR	.....	2841-1086
LANS	.....	2892-1137
RTD	.....	3150-1395

8 5/8 " 727 / 350SX, 5 1/2 " 3149 / 85SX, PORT COLLAR 2435 / 250SX  
NO CORES OR DSTS  
MIST - CO, PF (LKC J) 3086-89 W/4 SPF, AC 300G (15% MCA),  
SWB DWN, REC 10' FL (SCUM OIL) / 30", PF (LKC G) 2978-83  
W/4 SPF, SWB DWN, REC 2.9 BTF (94% OIL), AC 500G (15%  
MCA), SWB DWN, REC 8 BF (17% OIL), PF (LKC C) 2923-28 W/4  
SPF, AC 500G (15% MCR), SWB DWN, RE-AC 4000G (60 QUAL /  
20% NE), SWB DWN, REC 4 BTFPH (18% OIL), PF (DOUG) 2870-  
75 W/4 SPF, AC 500G (15% MCA), SWB DWN, REC 650' FL (10%  
OIL) / 15", PF (TOR) 2843-47 W/4 SPF, AC 400G (15% MCA),  
SWB DWN, RE-AC 1500G (28% NE), SWB DWN, REC 3 BTFPH  
(30% OIL), POP, P 16 BO & 100 BWPD, 5/22/85, COMMINGLED

COPYRIGHT 1985  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS