

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-21902-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 10-14S-13W  
990 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: DUMLER D Well #: 1  
County: RUSSELL Total Vertical Depth: 2424 feet

Operator License No.: 3134  
Op Name: MORRIS, TERRY E. DBA G L M COMPA  
Address: PO BOX 193  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2428	0	w/125 sxs cmt
SURF	8.625	245	0	w/unknown sxs cmt

**\$ 78.78**

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/10/2007 8:30 AM  
Plug Co. License No.: 31172 Plug Co. Name: L & M WELL SERVICING, INC.  
Proposal Rcvd. from: ARNIE MICHAELIS Company: GLM COMPANY Phone: (785) 483-1307

Proposed Plugging Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/10/2007 11:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 2200' - pumped 40 sxs 60/40 pozmix - 10% gel with 150# hulls.  
Pulled to 1100' - circulated with 40 sxs cement with 100# hulls.  
POOH. Pumped 50 sxs cement down casing.  
Max. P.S.I. 500#. S.I.P. 400#.  
Pumped 25 sxs down backside.  
Max. P.S.I. 600#. S.I.P. 450#.

Perfs:

INVOICED

DATE 2-12-07  
INV. NO. 2007061327

Remarks: QUALITY CEMENTING COMPANY.  
Plugged through: CSG

District: 04 Signed Case Morris  
(TECHNICIAN)

JAN 24 2007

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 07 2007  
CONSERVATION DIVISION  
WICHITA, KS

YOST OIL OPERATIONS

#1 "D" DUMLER

10-14-13W  
NW SW SW

BOX 811

RUSSELL, KS 67665

CTY RUSSELL

CONTR EMPHASIS DRLG.

GEOL

FIELD HALL-GURNEY

E 1807 KB

CM 4/13/82

CARD ISSUED

8/5/82

IP P 12 BO & 30 BWPD

WAB(LANG) 2360-2370

API 15-167-21,902

	+	+	+
	+	+	+
	+	+	+

LOG	TOPS	DEPTH	DATUM
SC		775	+1032
GR HAV		2324	- 517
DOVER		2352	- 545
LANG		2354	- 547
TARK		2396	- 589
RTD		2424	- 617

8-5/8" 245, 4 1/2" 2428/125sx

NO DST'S  
MICT - CO, PF (LANG) 40/2360-70, FRAC'D  
POP, P 12 BO & 30 BWPD, 7/9/82

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS