

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-02400-00-00  
Spot: NWSW Sec/Twnshp/Rge: 25-14S-13W  
1980 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: WEIMEISTER A Well #: 2  
County: RUSSELL Total Vertical Depth: 3166 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD   | 5.5   | 3142       | 0           | 125 SX  |
| SURF   | 8.625 | 340        | 0           | 115 SX  |

\$ 102,90

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/08/2007 11:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: KEVIN AXELSON Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/08/2007 1:30 PM KCC Agent: CASE MORRIS

**Actual Plugging Report:**

Perforated at 1300' and 700'.  
Ran tubing to 1550'.  
Circulated with 150 sxs 60/40 pozmix - 10% gel with 300# hulls.  
POOH. Tied onto casing and pumped 150 sxs cement.  
Max. P.S.I. 700#. S.I. P. 600#.  
Pumped 50 sxs down backside.  
Max. P.S.I. 500#. S.I.P. 300#.

**Perfs:**

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2874 | 2889 |      |          |

INVOICED

DATE 2-17-07  
INV. NO. 2007061328

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 07 2007

Remarks: QUALITY CEMENTING COMPANY.

CONSERVATION DIVISION  
WICHITA, KS

Plugged through: CSG

District: 04

*118*

Signed Case Morris  
(TECHNICIAN)

JAN 24 2007

*PK*

CITIES SERVICE OIL

#2

WEIDMEISTER

25-14-13W  
C NW SW

Contr.

RUSSELL

County

E 1709

Comm

3-31-42

Comp.

5-6-42

IP

59 BO / 59 BW

| Tops | Depth | Datum  |
|------|-------|--------|
| Anh  | 672   | + 1037 |
| TOP  | 2546  |        |
| LANS | 2848  |        |
| SOOY | 3136  |        |
| TD   | 3166  |        |

Casing

8" 3140

5" 3142

PB 3094

Perf 47/2881-89

A/1000

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

