

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21457-00-00
Spot: S2NESENE Sec/Twnshp/Rge: 12-15S-14W
3465 feet from S Section Line, 330 feet from E Section Line
Lease Name: EICHMAN A Well #: 23
County: RUSSELL Total Vertical Depth: 3403 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		758		
PROD	5.5	3402	0	w/200 sxs cmt
SURF	8.625	353	0	w/225 sxs cmt

\$ 110.60

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/12/2007 11:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KEVIN AXELSON Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/12/2007 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 1550'.
Circulated with 250 sxs 60/40 pozmix - 10% gel cement.
POOH.
Pressured backside to 500# P.S.I. (DV at 758' w/175 sxs)
Pumped 20 sxs down casing.
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

INVOICED
DATE 2-12-07
INV. NO. 2007061328

Remarks: QUALITY CEMENTING COMPANY.

Plugged through: CSG

District: 04

103

Signed

Case Morris

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

FEB 07 2007

CONSERVATION DIVISION
WICHITA, KS

JAN 24 2007

PKP

CITIES SERVICE CO
 700 SUTTON PLACE #23 EICHMAN "A" C S/2 NE SE NE
 WICHITA, KS 67202
 CONTR EMPHASIS OIL OPER CTY RUSSELL

12-15-14W

GEOL _____ FIELD TRAPP
 E 1872 KB CM 6/12/80 CARD ISSUED 7/31/80 IP P 8 BO & 71 BWPD
 API 15-167-21,457 TOR 3009-11
 LANS 3079-3248 OA

+	+	+	+
+	+	+	+
+	+	+	+

SMP	TOPS	DEPTH	DATUM
HEEB	2978	-1106	
LANS	3043	-1171	
ARB	3345	-1473	
RTD	3403	-1531	
LOGGED			

8-5/8" 353/225sx, 5 1/2" 3402/200sx, DV
 TOOL @ 758/175sx
 DST (1) 3352-3360 (ARB)/30-30-30-60,
 REC 100' M, PKR FAILED, NO
 PRESSURES RECORDED
 DST (2) 3352-3360 (ARB)/15-30-30-60,
 REC 30' M, SIP 222-380#, FP 53-63/
 53-53#, BHT 100"
 MJCT - CO, PF (TOR) 4/3009-11, PF (LKC)
 8/3079-83, 10/3095-3100, 8/3130-34, 8/
 3138-42, 8/3151-55, 8/3244-48, AC
 3500 (15%), 203 BTL, SET RBP @ 3300,
 POP, COMMINGLED

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS