

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24929-00-00
Spot: ^{nw} ~~NE~~SESW ^{Per RBDMs} ~~KCC~~ PRT Sec/Twnshp/Rge: 30-20S-11W
1250 feet from S Section Line, 2000 feet from W Section Line
Lease Name: SOEKEN Well #: 1-30
County: BARTON Total Vertical Depth: 3453 feet

Operator License No.: 31725
Op Name: SHELBY RESOURCES LLC
Address: 1658 COLE BLVD., STE 205
LAKWOOD, CO 80401

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3451	0	175 SX CMT.
SURF	8.625	565	0	300 SX CMT.

\$ 112.22

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/28/2006 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/28/2006 3:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 3070' and dumped 5 sxs cement.
Cut off at 2480'.
Pulled to 1350' - pumped 100 sxs 60/40 pozmix - 10% gel with 300# hulls.
Pulled to 570' - pumped 40 sxs cement with 100# hulls.
Pulled to 200' - circulated with 40 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3396	3402		
3382	3388		
3364	3374		
3355	3361		
3301	3303		
3169	3171		
3147	3150		
3134	3138		

INVOICED
DATE 2-12-07
INV. NO. 2007061330

Remarks: COPELAND CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Case Morris

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

FEB 07 2007

CONSERVATION DIVISION
WICHITA, KS

JAN 26 2007

PVT

SHELBY RESOURCES LLC
HAYS KS 67601

30-20S-11W
1250' FSL & 2000' FWL, SEC

#1-30 SOEKEN

site: 4-3/4 S OF ELLINWOOD KS
contr: STERLING DRILLING #1

city: BARTON
field: KOWALSKY

API 15-009-24929

geol:
fr
date 04/13/2006 spd
date 04/19/2006 drlg
comp 04/25/2006 card
issued 11/27/2006 last
revised 12/25/2006

ELV: 1809 GL
topsdepth/datum
PBTD3425 -1616
RTD3453 -1644
NO TOPS RPTD

IP status:
D&A, ARB , 11/20/2006
NOTE: INFO RELEASED 12/25/2006 - ADDED MISC INFO
CSG: 8-5/8" 565 / 300 SX (ALT 1), 5-1/2" 3451 / 175 SX
COMMENT: MI & RURT 4/19/2006
NO CORES
DSTS TAKEN - DETAILS NA
TRGT ZN: ARB (OIL), PTD 3400 (ARB), MICT - CO, PF (ARB)
3355-3361, 3364-3374, 3382-3388, 3396-3402, SWB DWN, NON-
COMMERCIAL, PF (LKC) 3134-3138, 3147-3150, 3169-3170,
3301-3303, SWB DWN, NON-COMMERCIAL, SI - EVAL,
DECISION MADE TO P & A 11/20/2006 - NO OTHER INFO
AVAILABLE - TEMP COMP 11/27/2006

COPYRIGHT 2006
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS