

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-00571-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 8-12S-15W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: OSWALD C Well #: 1
County: RUSSELL Total Vertical Depth: 3037 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PARKWAY, BLDG
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	15.5	391		
PROD	5.5	2995	0	375 SX
SURF	8.625	2295	0	w/unknown sxs cmt

\$ 98.70

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/29/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/29/2006 5:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 1700' and 920'.
Ran tubing to 2500' - pumped 100 sxs 60/40 pozmix - 10% gel.
Pulled to 1250' - circulated with 450 sxs cement.
POOH. Tied onto casing and circulated up 6" - 8" - 10" annulus with 290 sxs cement.
Cement started coming into cellar.
Pumped 35 sxs down 12" annulus.
Max. P.S.I. 200#. S.I.P. 200#.
Pumped 30 sxs down 15" annulus.
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
2998	3037		
2506	2516		

INVOICED

DATE 2-12-07
INV. NO. 200 7061331

Remarks: QUALITY CEMENTING COMPANY AND COPELAND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

JAN 26 2007

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3
FEB 07 2007
CONSERVATION DIVISION
WICHITA, KS

PKT