

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: L. D. DRILLING, INC.

Address: 7 SW 26 AVE., GREAT BEND, KANSAS 67530

Phone: (620) 793 - 3051 Operator License #: 6039

Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 12/13/06 (Date)

by: KEN JEHLIK (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 135-24569-0000

Lease Name: SCHLEGEL TRUST

Well Number: 3

Spot Location (QQQQ): SW - NE - SW -

1590 Feet from ☐ North / ☒ South Section Line

1440 Feet from ☐ East / ☒ West Section Line

Sec. 31 Twp. 19 S. R. 24 ☐ East ☒ West

County: NESS

Date Well Completed: 12/13/06

Plugging Commenced: 12/13/06

Plugging Completed: 12/13/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
SURFACE		0	690'	8 5/8"	690	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @ 1700' w/ 50 sx., 2nd Plug @ 830' w/ 80 sx., 3rd Plug @ 400' w/ 50 sx.,

4th Plug @ 60' w/ 20 sx., 5th Plug @ Rathole w/ 15 sx., 6th @ Mousehole w/ 10 sx.,

Total 225 sx. of 60/40 Pozmix 6% Gel, 1/4# FloSeal per sx.

By JetStar Services, Plug Down @ 7:00 P.M. 12/13/06

Name of Plugging Contractor: H-2 Drilling, LLC

License #: 33793

Address: 1021 Eisenhower #102, Great Bend, KS 67530

Name of Party Responsible for Plugging Fees: L. D. DRILLING, INC.

State of KANSAS County, BARTON, ss.

SUSAN SCHNEWEIS

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) 7 SW 26 AVE., GREAT BEND, KANSAS 67530

SUBSCRIBED and SWORN TO before me this 2 day of FEBRUARY, 20 07

NOTARY PUBLIC - State of Kansas
BESSIE M. DeWERFF
My Appt. Exp. 5-20-09

Notary Public Bessie M. DeWerff

My Commission Expires: 5-20-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

FEB 05 2007

KCC WICHITA

Plg