

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Mull Drilling Company, Inc. Address: P.O. Box 2758, Wichita KS, 67201-2758 Phone: (316) 264-6366 Operator License #: 5144 Type of Well: D&A Docket #: N/A The plugging proposal was approved on: 12/11/06 by: Jerry Stapleton Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-185-23400-00-00 Lease Name: Garvin-Marmie Well Number: 1-14 Spot Location (QQQQ): E/2 - NE - SE - SW 990 Feet from North / South Section Line 2361 Feet from East / West Section Line Sec. 14 Twp. 22 S. R. 14 East West County: Stafford Date Well Completed: 12/11/06 Plugging Commenced: 12/11/06 Plugging Completed: 12/11/06

Show depth and thickness of all water, oil and gas formations.


Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Surface, 292', 8 5/8", 281', 0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. Bottom plug @ 3900' w/50 sx, 2nd plug @ 840' w/50 sx, 3rd plug @ 300' w/50 sx, top plug @ 60' w/20 sx cemented to surface. Rathole w/15 sx, no mousehole. Plug down @ 3:00 p.m. on 12/11/06. Allied Cementing. Used 185 sx of 60/40 Poz, 6% gel. Heavy mud in hole and between all plugs.

Name of Plugging Contractor: Sterling Drilling Company, Inc. License #: 5142 Address: Box 1006, Pratt KS 67124-1006

Name of Party Responsible for Plugging Fees: Mull Drilling Company, Inc. State of Kansas County, Sedgwick, ss.

Mark A. Shreve, President/COO (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the



(Signature) [Handwritten Signature] (Address) P.O. Box 2758 Wichita KS 67201-2758

SUBSCRIBED and SWORN TO before me this 6th day of February, 2007. Tannis L. Tritt, Notary Public. My Commission Expires: 3.26.07

RECEIVED KANSAS CORPORATION COMMISSION FEB 07 2007 CONSERVATION DIVISION WICHITA, KS Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Garvin-Marmie 1-14

LOCATION: NE SE SW
API: 15-185-23400-0000

Section 14 T 22s R 14w
Stafford County, Kansas

OWNER: Mull Drilling
CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 02-Dec-06
COMPLETED: 11-Dec-06

TOTAL DEPTH: **DRILLER** 3900 FEET
LOGGER 3898 FEET

Ground Elevation: 1926
KB Elevation: 1935

LOG

| | | | |
|--------|-----------|-------------------------------|--------------------------------|
| 0 - | 12 FEET | Top Sand | <i>From Water Well Driller</i> |
| 12 - | 54 FEET | Clay | |
| 54 - | 100 FEET | Sand and Gravel | |
| 100 - | 260 FEET | Sands and Clays | |
| 260 - | 810 FEET | Redbeds | |
| 810 - | 845 FEET | Anhydrite (Driller's) | |
| 845 - | 1420 FEET | Shales and Salt | |
| 1430 - | 3730 FEET | Limestone, Shale and Dolomite | |
| 3730 - | 3900 FEET | Arbuckle | |

CASING RECORDS

Surface Casing-8-5/8"

Spud at 12:45 pm on 12/02/06. Drilled 12-1/4" hole to 292'. Ran 7 joints of new, 24#, 8-5/8" surface casing, tallied 281.13', set at 292' KB. Cemented with 400 sx Common, 2% Gel, 3% CC. Cement did circulate. Plug down at 12:15 am on 12/03/06. Allied Cementing ticket # 22698. Welder strapped bottom 3 joints together and welded collars on remaining joints.

Plugging Data

Plugged well on 12/11/06 in this manner: Heavy mud in hole and between all plugs. Used 170 sx of 60/40 Poz, 6% Gel. Bottom plug at 3900' w/ 50 sx, 2nd plug at 840' w/50 sx, 3rd plug at 300' w/50 sx, top plug at 60 w/20 sx cemented to surface. Rathole with 15 sx, no mousehole. Plug down at 3:00 pm on 12/11/06. Allied Cementing ticket #26328. KCC notified of plugging on 12/12/06.

DEVIATION SURVEYS

1 degree(s) at 292 feet
1 degree(s) at 3495 feet

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 07 2007
CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., INC.

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: 26328
Great Bend
2100 PM

| | | | | | | | |
|--|-------------|-----------------------------------|------------|--------------------|----------------------|-------------------|--------------------|
| DATE 12-11-06 | SEC 14 | TWP. 25S | RANGE 14W | CALLED OUT 8:00 AM | ON LOCATION 11:00 AM | JOB START 1:00 PM | JOB FINISH 3:00 PM |
| LEASE Gasolin-Macmie | WELL # 1-14 | LOCATION 281 + K-19 SW, 25, 1/2 E | | COUNTY Stafford | STATE KS | | |
| OLD OR <input checked="" type="radio"/> NEW (Circle one) | | | North side | | | | |

CONTRACTOR Stedinger Drilling Rig #1

TYPE OF JOB Rotary plug

HOLE SIZE 7 1/2" T.D. 3900'

CASING SIZE _____ DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE 4 1/2" DEPTH 3900'

TOOL _____ DEPTH _____

PRES. MAX 200 PSI MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT Feed water

EQUIPMENT _____

PUMP TRUCK # 181 CEMENTER Rick H.
HELPER Kevin D.

BULK TRUCK # 341 DRIVER Steve T.

BULK TRUCK # _____ DRIVER _____

OWNER Mull Drilling

CEMENT AMOUNT ORDERED 185 sx 60/40 6% Gel
1/4# Flo-seal

| | | | | |
|--------------------|-------------|---|--------------|----------------|
| COMMON | <u>129</u> | @ | <u>10.65</u> | <u>1182.15</u> |
| POZMIX | <u>74</u> | @ | <u>5.80</u> | <u>429.20</u> |
| GEL | <u>11</u> | @ | <u>16.65</u> | <u>183.15</u> |
| CHLORIDE | | @ | | <u>183.15</u> |
| ASC | | @ | | |
| <u>Flo-seal 46</u> | | @ | <u>2.00</u> | <u>92.00</u> |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| HANDLING | <u>198</u> | @ | <u>1.90</u> | <u>376.20</u> |
| MILEAGE | <u>22.9</u> | @ | <u>1.99</u> | <u>392.01</u> |
| TOTAL | | | | <u>2654.11</u> |

REMARKS:

| | |
|--------------|--------------------------------------|
| 3900' | 50 Sx |
| 840' | 50 Sx |
| 300' | 50 Sx |
| 60' | 20 Sx |
| Rot Hole | 15 Sx |
| Total Cement | 185 sx 60/40 6% gel 1/4# Flo-seal |

SERVICE

DEPTH OF JOB 3900'

PUMP TRUCK CHARGE 955.00

EXTRA FOOTAGE @ _____

MILEAGE 22 @ 6.00 132.00

MANIFOLD @ _____

TOTAL 1087.00

PLUG & FLOAT EQUIPMENT

| | | |
|-------|---|----------|
| _____ | @ | _____ |
| _____ | @ | _____ |
| _____ | @ | _____ |
| _____ | @ | _____ |
| _____ | @ | _____ |
| TOTAL | | <u>0</u> |

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

CHARGE TO: Mull Drilling

STREET _____

CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE X K.D. Clark

X K.D. Clark RECEIVED
KANSAS CORPORATION COMMISSION
PRINTED NAME FEB 07 2007