

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-02286-00-00

API NUMBER May 1947

LEASE NAME Cabbage

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #3

1650 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 7 TWP. 9 RGE. 18 (X) or (W)

COUNTY Rooks

LEASE OPERATOR The Gene Brown Company

ADDRESS PO Drawer 220 Plainville, Ks. 67663

PHONE# (913) 434-4811 OPERATORS LICENSE NO. 5635

Date Well Completed May 1947

Character of Well oil

Plugging Commenced 6-29-1995

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-29-1995

The plugging proposal was approved on 6-23-95 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation LKC Depth to Top 3180 Bottom 3436 T.D. 3490

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				10 3/4	198	None
Production				5 1/2	3487	None
Production				2 1/2	3460	2100'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perf at 2050', 1450', 800' Ran tubing to 2000' Spot 80 sks cement with 100# hulls, Pulled tubing to 1000', spot 75 sks cement with 100# hulls and cement circulated. Pulled tubing Pumped 40 sks cement down 5 1/2 casing at 700 psi and shut in at 100 psi Hooked to 8 5/8 pumped 50 sks cement and 50# hulls at 400 psi Shut in at 50 psi Well Plugged (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co License No. N/A

Address Russell, Ks

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Gene Brown Company

STATE OF Kansas COUNTY OF Rooks, ss. AUG 24 1995

Thomas M. Brown (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thomas M. Brown

(Address) PO Drawer 220 Plainville, Ks 67663

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 19 1995

Bonita K. Schubert
Notary Public

My Commission Expires: July 2, 1997

