

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-02291-00-00

API NUMBER 7-22-54

LEASE NAME Cabbage

WELL NUMBER #8 NW-SW-SW

990 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 7 TWP. 9 RGE. 18 (E) or (W)

COUNTY Rooks

Date Well Completed 7-22-54

Plugging Commenced 2-12-93

Plugging Completed 2-12-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Gene Brown Company

ADDRESS PO Drawer 220 Plainville, Ks. 67663

PHONE# (913) 434-4811 OPERATORS LICENSE NO. 5635

Character of Well Oil

(Oil, Gas, ~~P.A.~~, ~~SWD~~, ~~Input~~, ~~Water~~, ~~Supply~~, ~~Well~~)

The plugging proposal was approved on 2-12-93 (date)

by Dennis Hamel -- verbal (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached? yes

Producing Formation L.K.C. Toronto Depth to Top 3222 Bottom 3417 T.D. 3462

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|-------------------|------|----|-------|--------|------------|
| | surface pipe | | | 8 5/8 | 248 | none |
| | production casing | | | 5 1/2 | 3486 | none |
| | production tubing | | | 2 7/8 | 3430 | 3000 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. order 300 sks 60/40 poz min - 10% gel - 1/4# Flowcel with 500# hulls. Pump cement slurry down 5 1/2 casing mixing 100# hulls every 10 bls Max psi. 500 with shut in 150 psi. Hook up to 8 5/8 pump 1/2 bl cement at 600 psi. well plugged 3:00pm 2-12-93

(If additional description is necessary, use BACK of THIS form.)

Name of Plugging Contractor Halliburton

Address Hays, Ks.

STATE CORPORATION COMMISSION

License No. 5287

MAR 5 1993

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Gene Brown Company


STATE OF Kansas COUNTY OF Rooks, ss.

Thomas M. Brown

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thomas M. Brown

(Address) P.O. Drawer 220 Plainville, Ks 67663



SUBSCRIBED AND SWORN TO before me this 26th day of February, 1993

Kathy A. Wise

Notary Public

My Commission Expires: 5-27-94