

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,699 ~~00-00~~

LEASE NAME DURHAM

WELL NUMBER #2

4950' Ft. from S Section Line

990' Ft. from E Section Line

SEC. 22 TWP. 22 SRGE. 12 (X) or (W)

COUNTY STAFFORD

Date Well Completed 9-21-90

Plugging Commenced 9-21-90 8:45 PM

Plugging Completed 9-21-90 10:00 PM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR L. D. Drilling, Inc.

ADDRESS R.R. 1 Box 183 B Great Bend, Kansas
67530

PHONE#(316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 21, 1990 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3688'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	332'	8 5/8"	332'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

50 sx. @ 690', 50 sx. @ 360', 10 sx. @ 40', 15 sx. in rathole

Total: 125 sx. 60/40 Pozmix, 6% Gel, 1/4# flo-seal per sack

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address Great Bend, Kansas 67530

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1990


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D. Drilling, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Greg Davidson (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Greg Davidson
Greg Davidson

(Address) R.R. 1 Box 183 B
Great Bend, Ks. 67530



SUBSCRIBED AND SWORN TO before me this 9th day of October, 19 90

My Commission Expires: 5-20-93
Notary Public
Bessie M. DeWerff

DRILLER'S WELL LOG

COMMENCED: 9-14-90
COMPLETED: 9-21-90

0-333 Surface
333-450 Red Bed
450-1115 Red Bed & Shale
1115-3681 Lime & Shale
3681-3688 Arbuckle

L. D. Drilling, Inc.
Durham #2
NW NE NE Sec. 22-22S-12W
Stafford County, Ks.

ELEVATION: 1865' GR 1870' KB

FORMATION DATA: (Sample)

Anhy	643-666 (+1227)
Heebner	3157 (-1287)
Tor.	3175 (-1305)
Douglas	3191 (-1321)
B. Lime	3289 (-1419)
L. K/C	3307 (-1437)
B. K/C	3537 (-1667)
Viola	3567 (-1697)
Simp. Shale	3618 (-1748)
Simp. Sand	3620 (-1750)
Arbuckle	3681 (-1811)
R.T.D.	3688 (-1818)

CASING:

8 5/8" Set @ 332' W/175 sx. 60/40
Pozmix, 2% Gel, 3% CC

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON)^{SS}


GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 9th day of October, 1990.

My Commission expires: 5-20-93

Bessie M. DeWerff
Notary Public: Bessie M. DeWerff



OCT 11 1990