

RECEIVED  
 9/12/01  
 SEP 12 2001  
 KCC WICHITA

API NUMBER 15-163-19066-00-01

LEASE NAME J. Werner

WELL NUMBER #4

TYPE OR PRINT  
 NOTICE: Fill out completely and return  
 to KCC's Div. office within 30 days.

330 Ft. from  N Line of Section (circle one)

2310 Ft. from  N Line of Section (circle one)

LEASE OPERATOR White Eagle Resources

ADDRESS 881 W. Chestnut Circle

CITY, STATE, ZIP Louisville, Col. 80027

PHONE#(877) 604-6888 OPERATORS LICENSE NO. 31430

Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

SPOT LOCATION NE - NE - NW

SEC. 7 TWP. 9 S. RGE 18 or  or

COUNTY Rooks

Date Well Completed 4-19-51

Date Plugging Commenced 8/16/01

Date Plugging Completed 8/16/01

The plugging proposal was approved on 8/10/01 (date)

by Rich Williams (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation(s) L-KC "A" "B" "H" "I" "J" + Arbuckle Depth to Top 3208 Bottom 3457 T.D. 3458  
 (8/15/SS)

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
		0	203	10 3/4		
		0	3460	5 1/2		

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 0 feet to 1104 feet each set.

Ran tubing to 1104, Pumped & Cleaned out to 1300'. Could not go lower due to parted or collapsed casing. Pumped 150 sxs of 60/40 pozmix w/200# hulls. Circ. cement. Pulled tubing. Pumped 175 sxs of 60/40 PM w/200# hulls. Maximum pressure was 200#. Shut in Pressure was 300#. Pumped 25 sxs w/100# hulls.  
 (If additional description is necessary, use BACK of this form.)

down 8 5/8. Circulated and shut in.

Name of Plugging Contractor Allied Cementing

License No. 0

Address 24 S Lincoln St. - Russell, Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: White Eagle Resources

STATE OF Colorado COUNTY OF Boulder, ss.

Randy Weigel (Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Randy Weigel

(Address) 2190 1/6 Rd Plainville, Ks.

SUBSCRIBED AND SWORN TO before me this 20<sup>th</sup> day of August, 192001

S. J. Stahl  
 Notary Public

My Commission Expires: 03-05-02



*al*