

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22,384-00-00

LEASE NAME Bartlett

WELL NUMBER 1

SPOT LOCATION NW SE SE

SEC. 8 TWP. 9 RGE. 18 ~~SE~~ (W)

COUNTY Rooks

Date Well Completed 6-12-84

Plugging Commenced 6-12-84

Plugging Completed 6-12-84

LEASE OPERATOR Southern States Oil Company

ADDRESS Box 1365, Great Bend, Kansas 67530

PHONE # (316) 792-2585 OPERATORS LICENSE NO. 5354

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? YES If not, is well log attached? _____

Producing formation D&A Depth to top _____ bottom T.D. 3530'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8-5/8"	260'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

25 sk @ 3510', 25 sk @ 1420', 100 sk @ 850', 40 sk @ 300', 10 sk @ 40', & 10 sk in RH.
50/50 Poz-mix, 6% Gel 3% CC 1 sk Cello Flake

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Sun Cementing License No. _____
Address Box 169, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Claude Blakesley (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as received that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION
8/17/84
AUG 07 1984
(Signature) Claude Blakesley

(Address) P.O. Box 1365, Great Bend, Ks.



CONSERVATION SWORN TO before me this 6 day of August, 1984
SUBSCRIBED AND SWORN
Wichita, Kansas

My Commission expires: June 24, 1985

Nadine K. Newkirk
Notary Public