

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: 3/30/06 (Date)

by: David Williams (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (if needed attach another sheet)  
Lansing Kansas City Depth to Top: 2874 Bottom: 2889 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-167-02400-0000

Lease Name: Weimeister

Well Number: A-2

Spot Location (QQQQ): C - NW - SW -  
1980 Feet from  North /  South Section Line

4620 Feet from  East /  West Section Line

Sec. 25 Twp. 14 S. R. 13  East  West

County: Russell

Date Well Completed: 5/42

Plugging Commenced: 1/18/07

Plugging Completed: 1/18/07 1/8/07 KCC PPT  
per CP 2/3 @ 1/31/0

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	340	8 5/8	340	0
	Production	Surface	3142	5 1/2	3142	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RU Quality Oilwell Cementing. Pumped 300# hulls & 100 sx 60/40 Poz w/10% gel @ 1550'. TOH w/50 jts 2 3/8" tbg. Hooked up to 8 5/8" surface. Pumped 50 sx 60/40 Poz w/10% gel. Pressured to 250 psi. Swedged into 5 1/2" csg. Mixed 100 sx 60/40 Poz w/10% gel. Pressured to 600 psi. SI csg. Plug job witnessed by Case Morris w/KCC, Hays.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606


Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Susan Sears, Operations Engineer (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Susan Sears

(Address) 250 N. Water, Suite 300; Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 25th day of January, 20 07

Susan Brady My Commission Expires: 11-4-07  
Notary Public

RECEIVED

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 JAN 29 2007

KCC WICHITA

PKG