

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-20406-00-0

LEASE NAME Hilgers #

WELL NUMBER #3

SPOT LOCATION SE NE NW

SEC. 8 TWP. 9 RGE. 18 (E) or (W)

COUNTY Rooks

Date Well Completed _____

Plugging Commenced 12-9-85

Plugging Completed 12-16-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Condor Energy

ADDRESS Box 108, Great Bend, Kansas 67530

PHONE # (316) 564-3307 OPERATORS LICENSE NO. 6016

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Six (6)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 3530'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	200'	None
				5-1/2"	3503'	1,018.18'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.
Dumped sand to 3180' and 5 sacks cement. Shot casing at 2000', 1500' and 1000'. Pulled 32 joints of 5-1/2" casing. Squeezed well with 50 sacks cement mixed with 2 sacks hulls, 12 sacks gel mixed with 2 sacks hulls, and 60 sacks 60/40 pozmix cement with 10% added gel mixed with 2 sacks hulls. Maximum pressure 800 psi and shutin 400 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111
Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 17th day of December, 1985

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton, County, Kansas
My Appt. Exp. 9-26-87

STATE CORPORATION COMMISSION
Iona M. Leatherman
Notary Public

My Commission expires: _____

DEC 18 1985