

15-163-03466-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


OR

Strike out upper line
when reporting plug-
ging of formations.

FORMATION PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rooks County. Sec. 8 Twp. 9 Rge. 18 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines C S 1/2 SW SE
Lease Owner The Palmer Oil Corporation
Lease Name Hilgers Well No. 1
Office Address 415 Union National Bank Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9/20/48 19
Application for plugging filed 9/20/48 19
Application for plugging approved 9/20/48 19
Plugging commenced 9/20/48 19
Plugging completed 9/20/48 19
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 3558 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	181'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3558 - 180 Heavy Mud
180 - 135 Plug - 15 sacks cement
135 - 30 Heavy mud
30 - Bottom of cellar - Plug - 10 sacks cement

10/23/48

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Palmer Oil Corporation
Address 415 Union National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
A. H. Smith (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. H. Smith


Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of October, 19 48

Bonnie Durall

Notary Public.

My commission expires 3/21/49



WELL LOG - HILGERS #1

WELL OWNER: The Palmer Oil Corporation
 CONTRACTOR: Braden and Greene Drilling Company
 Commenced: 9/9/48
 Completed: 9/23/48
 RESULTS: Dry Hole

Section 5-35-15W
 Location: 6 S/ SW 22
 County: Rocks
 Elevation: 2079 D.F.

Casing Record
 8 5/8" - 181' cemented 110 yards

Surface & clay	0	70
Shale & shells	70	130
Blue Shale	130	181
Shale	181	585
Sand	585	615
Red bed	615	650
Shale & shells	650	790
Sand	790	815
Shale	815	900
Shale & shells	900	1430
Anhydrite	1430	1465
Shale & shells	1465	1900
Iron & shale	1900	1925
Red bed & shale	1925	1955
Shale & lime	1955	2075
Red bed & shells	2075	2200
Shale & shells	2200	2370
Shale & lime	2370	2455
Shale & shells	2455	2485
Sandy lime	2485	2520
Shale & lime	2520	3165
Lime	3205	3558 T. D. in conglomerate

Formation from D. F.
 Hestner 3232
 Lansing 3258
 Conglomerate 3522

Drill Stem Test - 3320' Packer set at 3305' Tool open 15 minutes when packer gave way - Recovered 330' of mud - no show oil, no show water.

This is to certify that the above is a true and correct log, according to the daily drilling reports.

THE PALMER OIL CORPORATION

A. H. Smith

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS

Subscribed and sworn to before me, a Notary Public in said county and state this 22nd day of October, 1948.

Bernie Duval
 Notary Public

My Commission expires 3/21/49.

PLUGGING
 No. 8 T 9 182
 BOOK PAGE 57 4V