

15-163-21127-00-00

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 - - (of this well)

Operator's Full Name FRONTIER OIL COMPANY
Complete Address 1437 N. FRANKLIN, RUSSELL, KANS. 67665
Lease Name HILGERS "A" Well No. #2
Location SW-SW-SW Sec. 8 Twp. 9 Rge. 18 (E) (W) W
County ROCKS. Total Depth 3576 FE
Abandoned Oil Well X Gas Well Input Well SWD Well D&A
Other well as hereafter indicated

Plugging Contractor ROCKHOLD ENGINEERING, INC.
Address BOX 698 - GREAT BEND, KANS. License No. 670
Operation Completed: Hour 10:45 ^{AM} Day 26 Month SEPT Year 1980

The Above well was plugged as follows:

8 5/8" 285 FE SP. CUL w/175 ST - 4 1/2" SET @ 3574 FE w/200 ST
PERF'S - TOP. 3444 FE - BOTTOM SAND TO 3394 AND w/4 ST CMT.
SHOT PIPE @ - 2600' - 2400' - 2200' - 2000' - 1900' RECOVERED 1800 FE
ORDERED - 140 ST 50/50 Pozmix 6% GEL. - 18 ST GEL. - 4 ST HULL'S - 8 5/8" PLUG.
PUMPED IN WITH PUMP TRUCK.
PUT IN 3 ST HULL'S - 10 ST GEL. - 70 ST CMT. - 8 ST GEL. - 1 ST HULL'S
RELEASED PLUG. 9 70 ST CMT. - MAX. PRESSURE 250 LBS
CEMENTED BY FILLED CMT.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10-2-80
INV. NO. 3238W

Signed: [Signature]
Well Plugging CORPORATION
RECEIVED
CORPORATION, COMMISSION
9/30/80
SEP 30 1980
CONSERVATION DIVISION
Wichita, Kansas