

6-29

4-041690

15-163-02286-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 5-1947

SW NW SW/4 SEC. 07, 09 S, 18 W
1650 feet from S section line
4950 feet from E section line

Operator license# 5635

Lease: Cabbage Well # 3

Operator: The Gene Brown Company

County: Rooks

Address: P.O. Drawer #220
Plainville, Kansas 67663

Well total depth 3460 feet
Conductor Pipe: 0 inch @ 0 ft
Surface pipe 8 5/8 Inch @ 1983 ft
w/100 sxs.

112.45

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kanas 67665

Company to plug at: Hour: 10:00A.M. Day: 29 Month: June Year: 1995

Plugging proposal received from: Tom Brown

Company: The Gene Brown Company Phone:

Were: 5 1/2" casing set at 3487' w/150 sxs. cement. Perf. at 3180' - 3436'. Salt at 1950' - Anhy. at 1450' - Dakota at 800'. T.O.F. at 1950' - tubing.

Ordered 300 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:30 P.M., Day: 29, Month: June, Year: 1995

Actual plugging report: Perf casing at 1950' - 1450' - 800'. R.I.H. with tubing to 1950'+. Spotted 80 sxs. with 200# hulls. At 950' spotted 75 sxs. with 200# hulls. At surface squeezed casing with 40 sxs. additional cement to 300# P.S.I. Hooked-up to 8 5/8" S.P. - squeezed with 50 sxs. cement and 100# hulls to 400# P.S.I. Job completed.

Remarks:

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did[X] / did not[] observe the plugging.

Dennis J. Hamel
(agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 21 1995
WICHITA KANSAS
Form CP-2/3

INVOICED

DATE 7-25-95

INV. NO. 43161

6-29

110