

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21275-00-00
Spot: CSEENENW Sec/Twnshp/Rge: 7-9S-18W
4390 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: WERNER Well Number: 6
County: ROOKS Total Vertical Depth: 3545 feet

Operator License No.: 31430
Op Name: WHITE EAGLE RESOURCES CORP.
Address: 881 W. CHESTNUT CIRCLE
LOUISVILLE, CO 80027

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 207 140 SX CMT
Production: Size 5.5 feet: 3544 130 SX CMT
Liner: Size feet:

\$ 115.21

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/15/2001 9:00 AM

Plug Co. License No.: 31430 Plug Co. Name: WHITE EAGLE RESOURCES CORP.

Proposal Rcvd. from: RANDY WEIGEL Company: WHITE EAGLE RESOURCES CORP. Phone: (785) 434-4900

Proposed 5 1/2" set at 3544' w/130 sxs.
Plugging D.V. Tool at 1457' w/370 sxs.
Method: Perfs 3130' - 3395'.
PBTD 3515'. Fluid level 1800'.
Ordered out 285 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 08/15/2001 10:30 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 5 sxs 60/40 pozmix - 10% gel down 8 5/8".
Max. P.S.I. 600#. S.I.P. 100#.
Hooked up to 5 1/2" casing - pumped 280 sxs 60/40 pozmix - 10% gel with 500# hulls.
Max. P.S.I. 1500#. S.I.P. 500#.

RECEIVED
8/20/01
AUG 20 2001
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

8-20-01

NV NO

2002060265

AUG 17 2001

ENERGY RESERVES GROUP

925 PATTON ROAD

#6 WERNER

7-9-18W

SE NE NW

GREAT BEND, KS 67530

CONTR EMPHASIS OIL OPERATIONS CTY. ROOKS

GEOL GERALD WEHLI

FIELD BARRY SE

E 2052 KB CM 4/18/81 ^{CARD}ISSUED 7/16/81 P 11 BOPD & 87 BWPD

+	°	+
+	+	+
+	+	+

SHAW(TOP) 3130-3156
LANS 3260-3395
(NEW PAY) OA

API 15-163-21,275

LOG	TOPS	DEPTH	DATUM
ANH		1445	+ 607
B ANH		1483	+ 569
TOP		2974	- 922
HEEB		3180	-1128
TOR		3202	-1150
LANS		3220	-1168
B KC		3430	-1378
ARB		3469	-1417
LTD		3474	-1422
RTD		3545	-1493

8-5/8" 207/140sx, 5 1/2" 3544/130sx,
DV TOOL @ 1457/370sx

DST (1) 3091-3155/30-62-58-120,
REC 186' SL OIL SPTD M, SIP
979-952#, FP 63-81/108-144#,
HP 1636-1627#, BHT 98°

DST (2) 3304-3352/30-60-60-123,
REC 75' M, SIP 253-253#, FP 44-
52/70-70#, HP 1683-1674#, BHT
98°

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

(OVER)

ENERGY RESERVES GROUP

#6 WERNER

7-9-18W

SE NE NW

DST (3) 3360-3440/30-60-60-120,
REC 220' THIN M W/FEW SPTS O,
SIP 949-931#, FP 35-78/78-131#,
HP 1838-1798#, BHT 98°

DST (4) 3464-3474/30-60-60-120,
REC 1550' SL MDY & SL OW, SIP
952-952#, FP 54-350/377-683#,
HP 1897-1852#, BHT 100°

MICT - CO, PF (LANS) 12/3392-95, 16/
3306-10, 16/3260-64, 16/3152-56,
(TOP) 16/3130-34, AC 5000 GAL, SWB
LD, R&T, POP