

4-070181

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-21,244 -00-00

NW NW NE /4 SEC. 07, 09 S, 18 W
4950 feet from S section line
2310 feet from E section line

Operator license# 6901

Lease: Joe Werner Well # 2

Operator: Bowman Oil

County: Rooks 112.42

Address: 805 Codell Road
Codell, Kansas 67663

7/13

Well total depth 3459 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 207 feet
W/135 sxs.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Bowman Oil License# 6901

Address: 805 Codell Road - Codell, Kansas 67663

Company to plug at: Hour: 9:00 A.M. Day: 13 Month: July Year: 2000

Plugging proposal received from: Don Bowman

Company: Bowman Oil Phone: 785-434-2286

Were: 5 1/2" set at 3457'. Tubing stuck and parted at 2500' with Dakota sand.

Fluid level 300'.

Perforate 1950' - 1450' - 800'. Run tubing to plug.

Ordered out 275 sxs 60/40 pozmix - 10% gel with 500# hulls.

RECEIVED
STATE CORPORATION COMMISSION
7/18/00
11 18 2000

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All , Part , None

Completed: Hour: 4:00 P.M., Day: 13 Month: July Year: 2000

Actual plugging report: L-K Wireline hit bridge at 1170'. Ran 62 joints 2 3/8" tubing.
L-K Wireline perforated at 1950'. Ran tubing to 2460'. Allied pumped 80 sxs 60/40 pozmix - 10% gel. Pulled tubing to 750'. L-K Wireline perforated 1450' and 800'. Ran tubing back to 1500' - top of cement. Allied pumped 160 sxs 60/40 pozmix - 10% gel with 200# hulls. Cement circulated. PTOH. Squeezed 25 sxs with 100# hulls. Max. P.S.I. 500#. S.I.P. 400#. Hooked up to backside - pumped 40 sxs with 100# hulls. Max. P.S.I. 700#. S.I.P. 200#.

Remarks:

Condition of casing(in hole): GOOD BAD X

Bottom plug(in place): YES , CALC , NO

Plugged through TUBING , CASING

Anhy.plug: YES NO

Dakota plug: YES , NO

Elevation: 2032 GL

I did / did not observe the plugging

Richard Williams
(agent)

INVOICED 10

DATE 7/19/00

INV. NO. 1060092

Form CP-213

Handwritten initials MB