

4-041974

4-24

API Number: 15-163-22,840-0000 KCC  
19 AB

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

SE SE NE /4 SEC. 19, 10 S, 18 W  
2970 feet from S section line  
330 feet from E section line

Operator license# 6931

Lease: H. Berland Well # B-2

Operator: Bowman Oil Company

County: Rooks 125.29

Address: 805 Codell Road  
Codell, Kansas 67630

Well total depth 3855 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 212 Feet  
W/130 sxs cmt.

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 24 Month: April Year 1998

Plugging proposal received from: Don Bowman

Company: Bowman Oil Company Phone: -

Were: 5 1/2" casing set at 3851' w/125 sxs cement. Perfs at 3792' - 3798'.  
D.V. Anhy. At 1684' with 400 sxs.  
Ordered 200 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel  
Plugging operations attended by agent? All , Part [ ], None [ ]

Completed: Hour: 2:00 P.M., Day: 24, Month: April, Year: 1998

Actual plugging report: R.I.H. with tubing 2200'. Spotted 190 sxs cement with 200# hulls to circulate at surface. P.O.O.H. with tubing and squeezed casing with 25 sxs cement. Max. P.S.I. 700#. S.I.P. 200#. 8 5/8" S.P. Pressured-up to 700#.

Remarks:  
Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_ CASING . Elevation: \_\_\_\_\_ G.L. \_\_\_\_\_

I did  / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)  
Form CP-2/3

INVOICED  
DATE MAY 14 1998  
INV. NO. 50553  
4-24

MAY 13 1998  
1998