

1120469

9-21

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,699-00-00

NW NE NE, SEC. 22, T 22 S, R 12 W/EX

4950 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Durham Well # 2

Operator: L.D. Drilling, Inc.

County Stafford 119.86

Name & Address RR 1, Box 183 B

Well Total Depth 3688 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 332

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 8:30 p.m. Day: 21 Month: 9 Year: 19 90

Plugging proposal received from Bessie

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 643-660'
1st plug at 690' with 50 sx cement, 2nd plug at 360' with 50 sx cement,
3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 p.m. Day: 21 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 690' with 50 sx cement,

2nd plug at 360' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

SEP 25 1990

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-2-90

Signed Duane Rankin (TECHNICIAN)

INV. NO. 29478