

15-163-02291-00-00¹⁸R

4-041445

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 7-22-54

NW SW SW /4 SEC. 07, 09 S, 18 W
990 feet from S section line
4950 feet from E section line

Operator license# 5635 Lease Cabbage well # 8

Operator: Gene Brown Company County Rooks

Address: Box 220 Well total depth 3486 feet ^{113.29}
Plainville, Kansas 67663 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 248 feet
w/185 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 2:00P.M. Day: 12 Month: February Year: 93

Plugging proposal received from: Tom Brown

Company: Gene Brown Company Phone: -

Were: 5 1/2" casing set @ 3486' w/175 sx. cement. Perf. @ 3200' -
3400'. Anhy. - D.V. @ 1435' w/480 sx. Top of tubing fish @ 3000'.
Hole open to perfs. Laid out tubing - 2/5/93.
Ordered 300 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 3:00P.M., Day: 12, Month: February, Year: 93

Actual plugging report: Pump down 5 1/2" casing: 300 sx. 60/40 pozmix
10% gel. with 1/4# flocele plus 500# hulls mixed in cement at a rate
of 100# per 10 bbl. slurry. Max. P.S.I. 500#. S.I. 150#.
Hooked-up to 8 5/8" S.P. and pressured-up to 600# with 1/2 bbl. slurry.

Remarks: Top of fluid 750'. Anhy. 1430'.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 2079 GL

I did X] did not] observe the plugging.

INVOICED
DATE 3-24-93
SERIAL NO. 37507

Dennis L. Hamel
#10
(agent)

RECEIVED
STATE CORPORATION COMMISSION
3/23/93
MAR 23 1993
CONSERVATION DIVISION
Wichita, Kansas