

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01647-00-01
Spot: SENW Sec/Twnshp/Rge: 35-9S-25W
3315 feet from S Section Line, 3411 feet from E Section Line
Lease Name: SPIES D Well #: 2
County: GRAHAM Total Vertical Depth: 4050 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	3.5	3748		75 SX CMT.
PROD	5.5	4040		75 SX CMT.
SURF	8.625	150		75 SX CMT.

\$ 131.63

Well Type: EOR UIC Docket No: E16551.1 Date/Time to Plug: 02/07/2007 2:00 PM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/07/2007 5:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Tied onto 3 1/2" - mixed and pumped 120 sxs with 500# hulls. S.I.P. 400#.
Tied onto 3 1/2" x 5 1/2" annulus - pumped 5 sxs cement. S.I.P. 500#.
Tied onto 8 5/8" x 5 1/2" annulus - pumped 100 sxs cement. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3837	4021		LKC
3824	3831		TOR

INVOICED


DATE 2-15-07
INV. NO. 0007061340

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

RECEIVED

FEB 12 2007

KCC WICHITA

Form CP-2/3


FEB 08 2007



EMPIRE DRILLING & _____ #2 D. SPIES _____ 35-9-25W
 N. APPLEMAN CO. _____ C SE NW
 Contr. _____ EMPIRE DRLG _____ GRAHAM _____ County
 E 2553RB Comm. 1-24-60 Comp. 2-26-60 IP 166 BOPD

Tops	Depth	Datum
ANH	2178	+375
HEEB	3800	-1247
TOR	3824	-1271
LANS	3837	-1284
TD	4050	-1497

Casing
 8" 150
 5" 4040
 DST 3810-35/1 HR, 6' MUD, BHP 0#
 DST 3834-50/1 HR, 60' G, 1140' SW, SC
 0, BHP 1150#
 DST 3864-80/1 HR, 1165' MDY SW, BHP 1175#
 DST 4007-30/1 HR, 1650' G, 120' OCM, 30'
 VH OCM, 90' OIL, BHP 560#
 DST 4027-50/1 HR, 12' MUD, W OIL SPTS,
 BHP 0#
 PERF: 4040-50: ACID 3000
 EMOR POOL 12 BOPH



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS