

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20414-00-01
Spot: SWNWSW Sec/Twnshp/Rge: 4-23S-21E
1590 feet from S Section Line, 4805 feet from E Section Line
Lease Name: GADDIS Well #: 110 I
County: ANDERSON Total Vertical Depth: 799 feet

Operator License No.: 31788
Op Name: VEENKER RESOURCES, INC.
Address: PO BOX 14339
OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	792	0	
SURF	7	20	0	

\$ 35

Well Type: EOR UIC Docket No: E16816.37 Date/Time to Plug: 07/01/2004 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: DALE MALEY Company: VEENKER RESOURCES, INC. Phone: (405) 844-1600

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO 792' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE WELL FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 07/01/2004 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE WELL TO T.D.. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE WELL AT SURFACE. THE 1" PIPE WAS REMOVED. THE WELL HAD A SHALLOW SEAK IN THE CASING. A 2" PACKER WAS RAN INTO THE WELL TO 20' ON 1", AND THE PACKER SET, AND CEMENT WAS SQUEEZED THROUGH THE 1" INTO THE WELL AND THE WELL WAS SHUT IN. 100 SACKS OF CEMENT WERE PUMPED INTO THE WELL.

Perfs:

Top	Bot	Thru	Comments
730	772		

RECEIVED
KCC DISTRICT #3
JAN 31 2007 CPT
CHANUTE, KS

INVOICED
DATE 2-14-07
INV. NO. 2007061336

Remarks: GPS LOCATION: 38.07187 N., 095.11233 W. (BY CPT 01/22/07)

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

FEB 08 2007

CONSERVATION DIVISION
WICHITA, KS

[Handwritten initials]