

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23404-00-00

Spot: SESESE

Sec/Twnshp/Rge: 36-15S-14W

480 feet from S Section Line,

330 feet from E Section Line

Lease Name: MICHAELIS A

Well #: 3

County: RUSSELL

Total Vertical Depth: 3380 feet

Operator License No.: 32325

Op Name: POPP OPERATING, INC.

Address: 191 NE 150 RD. PO BOX 187
HOISINGTON, KS 67544

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comment</u>
<u>SURF</u>	<u>8.625</u>	<u>835</u>		

\$ 109.85

Well Type: DH

UIC Docket No:

Date/Time to Plug: 01/19/2007 5:00 PM

Plug Co. License No.: 31548

Plug Co. Name: DISCOVERY DRILLING

Proposal Rcvd. from: TOM ALM

Company: DISCOVERY DRILLING

Phone: (785) 623-2920

Proposed Plugging Method: Order 155 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES

WitnessType: NONE

Date/Time Plugging Completed: 01/19/2007 8:00 PM

KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 3275' w/25 sxs.
2nd. Plug at 875' w/50 sxs.
3rd. Plug at 400' w/45 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

INVOICED

DATE 2-15-07

INV. NO. 2007061346

Remarks: QUALITY CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

(TECHNICIAN)

RECEIVED

Form CP-2/3

FEB 12 2007

KCC WICHITA

FEB 08 2007