

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-23868-00-00
Spot: S W N W S W Sec/Twnshp/Rge: 4-23S-19E
1485 feet from S Section Line, 1155 feet from W Section Line
Lease Name: GOINS Well #: 1
County: ANDERSON Total Vertical Depth: 834 feet

Operator License No.: 33135
Op Name: GARY C. SPLANE
Address: PO BOX 254
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	834	0	
SURF	6	20	0	

\$ 35.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/06/2007 12:00 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Revd. from: GARY SPLANE Company: GARY SPLANE Phone: (620) 433-1292

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO 833.6' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/06/2007 1:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 800 PSI. 30 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
KCC DISTRICT
FEB 7 2007 CPT
CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
782	788	CSG	

INVOICED

DATE 2-15-07
INV. NO. 2007061347

Remarks: THIS WELL WAS GPS'ED ON 02/06/07 AS GOI 01 AT 38.07122N & 095.33173W. CPT

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

RECEIVED
FEB 12 2007 Form CP-2/3
KCC WICHITA

[Signature]