

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

1/2/68
JAN 2 1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Clinton Oil Company

Complete Address 6810 West Highway 54 Wichita, Ks.

Lease Name E. A. Thompson Well No. 2

Location NE SW NE Sec. 6 Twp. 9 Rge. 18 (E) (W) X

County Rooks Total Depth 3490'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knights Casing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 5 P Day 30 Month 12 Year 1967

The above well was plugged as follows:

Total Depth 3490' 8 5/8 csg set at 205' cwc 140 sc.

6" csg set at 3490' cw 300 sc cement.

PBTD 3457 with top perf. at 3234'

Filled with sand to 3200' and dumped 5 sc cement with dump bailer.

Recov. 1607' of 6" csg.

Pumped down 8 5/8 csg with 35 sc gel W/4 hulls., and 150 sc cement.

Cement (0-50) Gel (50-250) Cement (250-680) Gel 680 to TD.

I hereby certify that the above well was plugged as herein stated.

ENCLOSURE

Signed: R. W. Mansel
Well Plugging Supervisor

1-2-68

7015-W