

15-163-03353-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW SE SW

SEC. 6 TWP. 9 RGE. 18 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Gick

Operator B & R Drg, Inc Address Russell, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3480 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 202' circulated with cement - 5 1/2" at 3473' with  
175 sax cement behind.

Filled with chat to 3460', set 4 sax cement with dump bailer,  
pulled 900' 5 1/2", filled hole with mud to 200', set rock  
and 15 sax cement, mud to 35', set rock and 10 sax cement  
to bottom cellar.

**PLUGGING**  
FILE SEC. 6 TWP. 9 RGE. 18 W  
ROCK PAGE 57 LINE 6

Received  
10/22/52

J. Edgar Perry  
District Conservation Agent

Date 10-18-52

CONSERVATION DIVISION  
Wichita, Kansas