

15-163-01530-00-00

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rocks _____

Location: SW NW NE Sec. 6 Twp. 9 Rge. _____ (E) _____ (W) 18

Name of Field: _____ Total Depth: 3486

I have this date completed supervision of plugging of:

Lease Name: Thompson Well No. 3

Operator's Full Name: Morganstern & Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor: Lynch Pipe Pulling Co

Address: Great Bend, Kans License No. 396

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 11AM Day 6 Month 8 Year 61

The above well was plugged as follows:

10 3/4" 204' circulated with cement - 6" OD 3478' with 300 sax cement.
sand and plugs to 2900', set 5 sax cement with dump bailer, pulled
1835' 6" to 500', circulated hole with heavy mud through 6" at 500'
(15 sax Gel), displaced 20 sax cement through 6" at 500', heavy mud to
170', displaced 20 sax cement through 6" at 170', heavy mud to ^{25'} 35', set
plugs and 10 sax cement to bottom cellar.

Mudding and cementing by Lynch Company pump truck.

Signed: *Jewel M. Ogden*
Conservation Division Agent

Reviewed: *Harold J. ...*
Field Supervisor

Remarks:

RECEIVED
STATE CORPORATION COMMISSION
8/14/61
AUG 14 1961
INVOICED
DATE 8/18/61
CONSERVATION DIVISION INV. NO. 3578-W
Wichita, Kansas