

15-163-20028-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
CONSERVATION COMMISSION
6/14/67
JUN 14 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name A. Ainsworth and Rains & Williamson Oil Co. Inc.,

Complete Address: 1425 Wichita Plaza Wichita, Kansas

Lease Name Hilgers Well No. 1

Location E 1/2 NW NW Sec. 8 Twp. 9 Rge. 18 (E) (W) X

County Rooks Total Depth 3583

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 4 P Day 11 Month 6 Year 1967

The Above well was plugged as follows:

RTD 3583' 8 5/8 csg set at 209' cwc 150 sc.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 25 sc cem.

thru drill pipe. Heavy mud to 200' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Prof. Massey
Well Plugging Supervisor

INVOICED

DATE 6/14/67

INV. NO. 5390-W